



Project Update Newsletter

August 2017

Construction has been making headway on the new McHenry Avenue bridge over the Stanislaus River. Crews have continued to work on the bridge foundations and bridge deck on the southern end of the bridge.

The McHenry Avenue Corridor Improvements project will enhance safety, inter-regional traffic circulation, and air quality.

Construction began in May 2017 and is on schedule to be completed by mid-2020.

Current Activities

- Construction continues on bridge foundations and superstructure.

Ongoing Work

- Falsework and formwork for the bridge deck on McHenry Avenue at the Southern end of the new bridge structure. Falsework is temporary construction used to support formwork which is a structure used for concrete to be poured.
- Construction of temporary trestle over the Stanislaus River to provide access to construct the bridge.
- Installation of stone columns.



Temporary trestle over the Stanislaus River to allow crews access for construction equipment.

Upcoming Construction Activities

September 2017

- Cast-In-Drilled-Hole (CIDH) piles and driven concrete piles. CIDH piles are concrete piles cast in holes used as a foundation for the bridge.
- Widening portions of East River Road and McHenry Avenue Intersection.
- No detours expected for the next few weeks.



Falsework and forming for the bridge deck at the Southern end on the Stanislaus River.

We apologize for any inconveniences.

Your patience and cooperation is much appreciated.

Yours truly,
The McHenry Construction Team



Call the project hotline at **(209) 497-5111**



Visit www.ImproveMcHenry.com



Email info@improvemchenry.com



Text **McHenry** to **41411**